

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19347-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 3-25S-3E  
355 feet from S Section Line, 2338 feet from E Section Line  
Lease Name: JOSEPH Well #: 1  
County: BUTLER Total Vertical Depth: 2747 feet

Operator License No.: 6407  
Op Name: FLOWERS PRODUCTION CO., INC.  
Address: PO BOX 249  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.38	140		15 SX
PROD	5.5	2733		35 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2009 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO. Phone: (316) 321-6650

Proposed Plugging Method: AS PER KCC RULES & REGS  
89.28

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/26/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,675' ESTABLISHED CIRCULATION, CONSOLIDATED OILWELL SERVICE MIXED & PUMPED 50 SXS CLASS A 4% CC AND DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 2,243'. TESTED CASING, HELD OK. RIH W/WIRELINE @ 250', AND SHOT SQUEEZE HOLES. TRIED TO ESTABLISH CIRCULATION BETWEEN CASINGS AND COULD NOT GET CIRCULATION ON BACKSIDE OF 8-5/8". SHUT DOWN. 3/26/2009, PLATED CASINGS TOGETHER. ESTABLISHED CIRCULATION BETWEEN CASINGS AND ON BACKSIDE OF 8-5/8" CASING PUMPING 3-4 BBL PER MIN. @ 200#, STARTED CEMENT, CONSOLIDATED MIXED & PUMPED 578 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED ON ALL STRINGS OF CASING. PLUG DOWN 5:00 P.M., 3-26-2009.

Perfs:

Top	Bot	Thru	Comments
2733	2747	OH	

KANSAS CORPORATION COMMISSION  
MAY 08 2009  
RECEIVED  
INVOICED

Remarks: CONSOLIDATED CEMENT TICKET #S, 20628 & 20629.

DATE 6-8-09  
INV. NO. 2009061575

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

SK

PBT