

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19348-00-00
Spot: SESWE Sec/Twnshp/Rge: 3-25S-3E
347 feet from S Section Line, 1700 feet from E Section Line
Lease Name: JOSEPH Well #: 3
County: BUTLER Total Vertical Depth: 2741 feet

Operator License No.: 6407
Op Name: FLOWERS PRODUCTION CO., INC.
Address: PO BOX 249
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	15.5	99		35 SX
PROD	5.5	2732		35 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO., INC. Phone: (316) 321-6650

Proposed Plugging Method: AS PER KCC RULES & REGS

89.08

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/26/2009 8:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,625' ESTABLISHED CIRCULATION, CONSOLIDATED OILWELL SERVICE MIXED & PUMPED 50 SXS CLASSA 4% CC AND DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 2,072'. TESTED CASING, HELD OK. RIH W/WIRELINE @ 250', AND SHOT SQUEEZE HOLES. DUG OUT CELLAR AND PLATED CASINGS TOGETHER. ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 419 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED ON ALL STRINGS OF CASING. PLUG DOWN @ 8:00 P.M., 3-26-2009.

Perfs:

INVOICED
DATE 6-8-09
INV. NO. 2009061575

KANSAS CORPORATION COMMISSION
MAY 08 2009
RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET #20630.

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

✓/JK

PKT