

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23151-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 3-25S-3E  
1058 feet from S Section Line, 1779 feet from E Section Line  
Lease Name: JOSEPH Well #: 5  
County: BUTLER Total Vertical Depth: 2810 feet

Operator License No.: 6407  
Op Name: FLOWERS PRODUCTION CO., INC.  
Address: PO BOX 249  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		140 SX
T1	2.375	2699		
PKR		2700		
PROD	5.5	2809		140 SX

Well Type: EOR UIC Docket No: E25887.1 Date/Time to Plug: 04/08/2009 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO., INC. Phone: (316) 321-6650

Proposed Plugging Method: AS PER KCC RULES & REGS  
91.33

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/08/2009 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,766' ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICE MIXED & PUMPED 50 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 2,502'. TESTED CASING, HELD OK. RIH W/WIRELINE @ 275' AND SHOT SQUEEZE HOLES. SWEDGED INTO 5-1/2" CASING, & ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICE MIXED & PUMPED 117 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2:30, 4-8-2009.

Perfs:

Top	Bot	Thru	Comments
2759	2766		CSG

INVOICED

DATE 6-8-09  
INV. NO. 2009061575

KANSAS CORPORATION COMMISSION  
MAY 08 2009  
RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET #20566. DOCKET #E-25,887

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK

PK