

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-19047-00-00  
Spot: SENESE Sec/Twnshp/Rge: 24-32S-2E  
1492 feet from S Section Line, 404 feet from E Section Line  
Lease Name: CONROD Well #: 1  
County: SUMNER Total Vertical Depth: 3134 feet

Operator License No.: 30037  
Op Name: GREEN, WAYNE L. DBA GREEN ENTER  
Address: 1007 152ND RD (ENTERPRISES)  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	75		100 SX
T1	2.375	3000		CMTD IN HOLE
PROD	5.5	3126		75 SX

Well Type: EOR UIC Docket No: E16485.1 Date/Time to Plug: 04/20/2009 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: WAYNE GREEN Company: GREEN ENTERPRISES Phone: (620) 455-3525

Proposed Plugging Method: PUMP TUBING STRING FULL OF CEMENT, CIRC CMT FROM 250-0 ON 5.5-8.625 ANNULAS  
  
101.86

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/20/2009 11:00 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

ON 1-19-2009, CONSOLIDATED CMTG TIED ONTO THE TUBING AND TOOK AN INJECTION RATE OF 2BBLS/MIN AT 950#. CONSOLIDATED CMTG THEN SWITCHED OVER TO CMT AND PUMPED 70 SKS OF CLASS A CMT 2% CALC. 2% GEL AND 1/4 LB OF FLOSEAL. SHUT IN PRESSURE 1000#. CAPACITY OF TUBING 50 SKS. TICKET #20769 ON 4-20-2009, DALE PHILLIPS WELL SERVICE RIGGED UP OVER THE WELL AND RUN 1" TUBING TO 250'. CONSOLIDATED CMTG PUMPED 95 SKS OF CMT IN THE 5.5-8.625 ANNULAS, BRING THE CMT TO SURFACE.

**Perfs:**

Top	Bot	Thru	Comments
3126	3134	OH	

INVOICED

DATE 6-8-09  
INV. NO. 2009061576


KANSAS CORPORATION COMMISSION  
MAY 08 2009

Remarks: CONSOLIDATED CMTG 60/40 4% GEL

RECEIVED

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

*JK*

*PT*