

4-18 15-109-20145-0001

6 031529

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,145-00-01

SW NE NW, SEC. 16, T 11 S, R 35 W/E

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Bertrand Well # 1

Operator: Mull Drilling Co. Inc.

County Logan 160.22

Name & Address Box 421

Well Total Depth 4930 feet

Ness City, Ks. 67560

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: Day: 18 Month: April Year: 19 91

Plugging proposal received from Monte

(company name) Kelso (phone)

were: 8 5/8 set at 251 w/225 sks cwc. 4 1/2 set at 4908 w/150 sks.

Perf 4312 - 4723. Order sand and common cement. Pull pipe.

RECEIVED

STATE CORPORATION COMMISSION Order 225 sks 65/3 5poz 10% gel 500 lbs. hulls. B. J. Services

4-25-1991
APR 25 1991

Hoxie water trucks. Open hole to fish w/bailer line.

CONSERVATION DIVISION
Wichita, Kansas Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:45AM Day: 18 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 4250 w/4 sks common cement on

sand w/bailer. Recovered 1618 of 4 1/2 casing w/shots at 1800 and 2500.

Sq 8 5/8 w/225 sks cement blend w/500 lbs. hulls mixed in to max psi

400 lbs. Close in psi 260 lbs. Plug complete. No pressure

encountered until last few sks.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(old / ~~xxx xxx~~) observe this plugging.

DATE 5-12-91

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

INV. NO. 31789

J.L.S.