

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-30029-00-00
Spot: SESE Sec/Twnshp/Rge: 21-27S-20W
677 feet from S Section Line, 707 feet from E Section Line
Lease Name: EINSEL CHARLES Well #: 2
County: KIOWA Total Vertical Depth: 4896 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	595		WITH 250 SX CMT
PROD	4.5	4896	625	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2009 11:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: VRATIL SERVICES, INC. Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

159.12

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2009 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

TOP OF TBG FISH (2 3/8") @ 1527'. CASING PARTED AT 625'. 4/24/09: PERFORATE @ 1300'. RUN 2 3/8" TBG INTO @ 1497'. SPOTTED 175 SX CMT. NO RETURNS TO POOR RETURNS TOWARD END OF SPOTTING PLUG. PULLED TBG OUT. SHUT DOWN. LET CMT SET. 4/27/09: RUN TBG IN & TAG TOC @ 675'. PULLED TBG UP TO 625'. CIRCULATED CMT FROM 625' TO SURFACE WITH 180 SX CMT. LAID TBG DOWN & TOP 8 5/8" SURFACE PIPE OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4879	4896		

INVOICED
DATE 6-9-09
INV. NO. 2009061583

KANSAS CORPORATION COMMISSION

MAY 11 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
MAY - 4 2009
KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

PST