

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21245-00-00
Spot: W2E2SE Sec/Twnshp/Rge: 26-31S-32W
1320 feet from S Section Line, 1040 feet from E Section Line
Lease Name: FEIERTAG Well #: 3-26X
County: SEWARD Total Vertical Depth: 5700 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 2 SX CMT
CIBP		5490		
SURF	8.625	1734		WITH 675 SX CMT
PROD	4.5	5698	3432	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/30/2009 2:00 PM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 5400' & 2 SX CMT. LOAD HOLE WITH GEL WATER. PUMP 50 SX CMT AT 1740'. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.
185.25

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2009 3:40 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SET CIBP @ 5400' WITH 2 SX CMT. 1ST PLUG LOAD HOLE WITH GEL WATER & PUMP 50 SX CMT AT 1751'. 2ND PLUG AT 609' WITH 50 SX CMT. 3RD PLUG AT 30' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5512	5526		MORROW
5435	5437		ATOKA

INVOICED
DATE 6-9-09
INV. NO. 2009061584

KANSAS CORPORATION COMMISSION
MAY 11 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
MAY - 4 2009

Signed

Jerry W. Stapleton
WIRT, II

(TECHNICIAN)

KCC DODGE CITY