

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21307-00-00
Spot: W2E2NE Sec/Twnshp/Rge: 29-19S-20W
3960 feet from S Section Line, 990 feet from E Section Line
Lease Name: WELLS - B Well #: 1
County: RUSH Total Vertical Depth: 4430 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		WITH 175 SX CMT
PROD	5.5	4407	0	100 SX ON BTM, 280 SX 1470' TO SURF

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2009 10:47 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL CORPORATION Phone: (620) 388-6143

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

143.98

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2009 11:52 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 40 SX CMT W/200# HULLS, 17 SX GEL SPACER & 150 SX CMT.
PRESSURED TO 2000#. SHUT IN AT 1500#. PRESSURED BACKSIDE TO 500#.
BACKSIDE WAS. FULL.

Perfs:

Top	Bot	Thru	Comments
4358	4365		

INVOICED
DATE 6-9-09
INV. NO. 2009061591

KANSAS CORPORATION COMMISSION
MAY 11 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: CSG

District: 01

RECEIVED
MAY - 4 2009

Signed Eric MacLaren
(TECHNICIAN)

KCC DODGE CITY