

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20146-00-00
Spot: SESWNESE Sec/Twnshp/Rge: 1-15S-43W
1530 feet from S Section Line, 900 feet from E Section Line
Lease Name: ARAPAHOE UNIT Well #: 109
County: WALLACE Total Vertical Depth: 5310 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	726	0	375 SX
PROD	4.5	5300	0	150 SX

172.58

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2009 9:00 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: HERSCHEL KENNEDY Company: CITATION OIL & GAS CORPORATI Phone: (719) 340-1150

Proposed Plug Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 100# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2009 12:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 726' w/375 sxs cement.
4 1/2" production casing set at 5300' w/150 sxs cement.
DV tool set at 1950' - cemented with 400 sxs cement.
CIBP set at 5150' - cement with 2 sxs cement.
Production casing filled with gelled water from 5150' to 600'.
Production casing perforated at 2880'.
Ran tubing to 2880' - pumped 30 sxs cement.
Pulled tubing to 2000' - pumped 30 sxs cement.
Pulled tubing to 1386' - pumped 15 sxs cement.
Pulled tubing to 773' - pumped 15 sxs cement.
Pulled tubing to 127'. Circulated cement to surface with 15 sxs.
Pulled tubing to surface.
Topped 4 1/2" production casing with 15 sxs cement.
Connected to 8 5/8" surface casing - pumped 125 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
5180	5190		MORROW

INVOICED

DATE 6-10-09

INV. NO. 2009061594

KANSAS CORPORATION COMMISSION

MAY 12 2009

RECEIVED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

PKT
CM


MAY 08 2009

STATE KANS COUNTY WALLACE
FIELD ARAPAHOEKAN (MORROW)
OPER TXO PROD
WELL 5 HIBBERT "A"
API 15-199-20146-0000
SPUD 03/14/1988
DTD 5310 LTD FTD MISS

Renamed Arapahoe UNIT # 109
RE-ISSUE

SESUWNESE
1-15S-43W
IRREG SEC
900FEL SEC

WELL CLASS 1530FSL
STATUS DO
COMP OIL 04/05/1988
PSTD



LOC 7 MI SW WESKAN, KS

Petroleum Information Corporation

W IPP 175 BOPD 60 BW
PROD ZONE: MORROW 5180-5185

EL: 3940 KB 3935 GR

CSGS: 8 5/8 @ 726 W/ 375 SACKS
4 1/2 @ 5300 W/ 150 SACKS
TBGS: 2 3/8 @ 5252
DRLG COMP 3/21/88 RIG REL 3/22/88

LOG TOPS:
STONE CORRAL 2896 +1044
TOPEKA 3978 -38
LANSING 4256 -316
MARMATON 4665 -725
FT SCOTT 4740 -800
CHEROKEE 4797 -857
ATOKA 4931 -991
MORROW 5102 -1162
MORROW B SD 5181 -1241
MORROW L LM 5203 -1263
MISS 5230 -1290
TD 5310 -1370

PERFS: MORROW PERF W/ 20/IT 5180-5185
ACID 250 GALS 7 1/2%

NO CORES OR DSTS

OPER ADDRESS: 1660 LINCOLN, DENVER, CO 80264
CONTR: MURFIN DRLG

REISSUE TO: CORRECT FORMATION @ TD, ADD LOG TOPS

REPLACEMENT FOR CARD ISSUED 10/18/88

KS R8-050190

Copyright 1990 Petroleum Information Corporation