

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03076-00-00
Spot: S2NESE Sec/Twnshp/Rge: 17-10S-23W
1650 feet from S Section Line, 660 feet from E Section Line
Lease Name: DIEBOLT LKC UNIT Well #: 1-4
County: GRAHAM Total Vertical Depth: 3905 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	277	0	225 SX
PROD	5.5	3899	0	150 SX

126.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2009 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 485 sxs 60/40 pozmix - 4% gel - 500# hulls.
Well originally drilled as Custer #4.
Squeezed 1892' w/200 sxs in 1972. CIBP at 3869'.
Operator elected all cement plug.
Junk in the hole. High fluids.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2009 1:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech shot two hole perf at 1150'.
Ran in hole with tubing to 2519'. Rigged to tubing - pumped 40 sxs neat - followed with 60 sxs cement with 200# hulls mixed in.
Pulled tubing to 1500'. Rigged to tubing - pumped 180 sxs cement with 300# hulls mixed in.
Pulled tubing to 750'. Rigged to tubing - pumped 70 sxs cement to circulate cement to pit area.
Pulled tubing. Topped 5 1/2" casing with 65 sxs cement.
Hole standing full.
Rigged to 8 5/8" casing - pumped 70 sxs cement to pressure.

Perfs:

Top	Bot	Thru	Comments
3836	3840		LKC

INVOICED
DATE 6-10-09
INV. NO. 2009061597

KANSAS CORPORATION COMMISSION

MAY 12 2009


RECEIVED

Remarks: WELL ORIGINALLY KNOWN AS CUSTER #4. QUALITY OILWELL CEMENTING COMPANY-TICKET #3096.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

MAY 05 2009

PKT

SUNRAY OIL

#4

CUSTER


17-10-23W
S2 NE SE

Contr. STICKLE DRILLING GRAHAM County

E 2385RB Comm. _____ Comp. 5-20-55 IP 321 BOPD

Tops	Depth	Datum	Casing
ANH	1925	460	8" 277 DST 3817-37/1 HR, 5" 3899 700' GSY OIL, 20' OIL & GCM, BHP 450#
			DST 3841-55/1/2 HR, 60' CL OIL 10' 0 & GCM, BHP 505#
LANS	3662	-1277	PERF 2 1/4 / 3836-40: 20 GOPH/3 HR ACID 1200: SWB 31 BO/3 HR: PB 3830: PERF 3824-28: 6.68 BOPH/4 HR: ACID 1750: SWB 25
			HAPPY POOL BOPH/4 HR
TD	3903	-1518	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



17-10-23W - S2 NE SE - 1120