

15-109-20013-00-00

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-23-1971
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name U. S. Signal Oil & Gas Company, 1971 Program.
Complete Address 125 Central Building, Midland, Texas.
Lease Name Collins Well No. 1
Location CNW-NW Sec. 34 Twp. 11 Rge. (E) (W) 37
County Logan Total Depth 5648'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza, Wichita, Kansas. License No.
Operation Completed: Hour 5:00 PM Day 18 Month 12 Year 1971

The above well was plugged as follows:

445'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1390'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 110 Cu. Ft. cement
thru DP from 1650' to 1325'. Pulled DP to 465' and displaced 30 Cu. Ft. cement thru
DP from 465' to 390'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4952-W