

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-109-00002-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Logan County, Sec. 24 Twp. 11S Rge. 37 (W)

Location as "NE/CNW/SW" or footage from lines Center SE SE  
Lease Owner Texaco Seaboard Inc.  
Lease Name F. C. Kleckner Well No. 1  
Office Address 614 Bitting Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed September 24 19 60  
Application for plugging filed 9-28- (Verbal) 19 60  
Application for plugging approved 9-27 19 60  
Plugging commenced 9-23 19 60  
Plugging completed 9-24 19 60  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production None 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, Victoria, Kansas  
Producing formation None Depth to top - Bottom - Total Depth of Well 4910 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	N O N E					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

TD to 600' w/hvy mud  
Wooden plug @ 600'  
600' - 541' w/cmt  
541'-310' w/hvy mud  
Wooden plug @ 310'  
310' to 251' w/cmt  
251' - 40' w/hvy mud  
Wooden plug @ 40'  
40' to Surf w/cmt.

RECEIVED  
STATE CORPORATION COMMISSION  
9-29-1960  
SEP 29 1960  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
M. C. HARRELL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell  
614 Bitting Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1960

My commission expires 6-30-64



15-109-00002-00-00

TEXACO, INC. - Operator

SIERRA PETROLEUM CO., INC. - Contractor

KLECKNER #1  
C SE SE  
Sec. 24-11S-37W  
Logan County, Kansas

Total Depth: 4910'

Commenced: 9-4-60  
Completed: 9-23-60

Casing:

8-5/8" Set at 314' KB

Cement:

with 200 sacks

FORMATION

DEPTH

Shale	316
Shale	985
Soft Lime - Chalk	1025
Shale & Shells	1824
Shale & Lime Shells	1965
Shale & Shells	2025
Anhydrite & Shale	2165
Salt & Shale	2324
Shale, Red Bed & Anhy.	2653
Shale & Red Bed	3005
Shale & Lime	3488
Lime	3733
Lime & Shale	4037
Lime	4708
Lime & Shale	4758
Lime	4910

STATE OF KANSAS  
9-27-1960  
SEP 27 1960

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Hensler

Subscribed and sworn to before me this 26th day of September, 1960.

Gerard Dieg  
Notary Public

My commission expires: 10-17-63

