

15-199-20036-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Wallace County, Sec. 28 Twp. 11S Rge. 39W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
430' EL, 2310' NL

Lease Owner Texas Oil & Gas Corporation  
Lease Name PEARCE "D" Well No. 1  
Office Address 200 W. Douglas, Suite 300, Wichita Ks  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed March 15 1980  
Application for plugging filed (verbally) March 15 1980  
Application for plugging approved (verbally) March 15 1980  
Plugging commenced March 15 1980  
Plugging completed March 15 1980  
Reason for abandonment of well or producing formation  
No commerical quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 5533'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

T.D. 5533'

Set 1st plug at 1500' with 60 sacks  
2nd plug at 260' with 30 sacks  
3rd plug at 40' solid bridge with 15 sacks  
rathole with 5 sacks.

Cemented with 50/50 posmix, 6% gel.  
Plug was down at 8:30 a.m., March 15, 1980.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1980



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1980  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG 15-199-20036-00-00

OPERATOR: Texas Oil & Gas Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Pearce "D" #1  
 LOCATION: 430' EL, 2310' NL, Section 28-11S-39W, Wallace County, Kansas  
 SPUD DATE: February 26, 1980  
 COMPLETION DATE: March 15, 1980

0	120	Sand and shale
120	285	Shale
285	1041	Shale and sand
1041	1909	Shale
1909	2700	Shale and sand
2700	2735	Anhydrite
2735	2800	Shale
2800	2986	Lime and shale
2986	3279	Shale and lime
3279	3378	Shale
3378	4036	Lime and shale
4036	4155	Lime
4155	4713	Lime and shale
4713	4760	Lime
4760	4820	Lime, shale and sand
4820	5268	Lime
5268	5415	Lime and shale
5415	5533	Lime
	5533	Rotary Total Depth

Spud hole at 2:00 p.m., February 26, 1980. Drilled 279' of 12 1/4" hole. Ran 7 joints of 10-3/4" - 30# casing. (Tally 279'). Set at 277' R.B. with 150 sacks of 50/50 posmix, 1/4# cel flake followed with 200 sacks of common cement 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 2:00 a.m., February 27, 1980.

T.D. 5533'. Set 1st plug at 1500' with 60 sacks, 2nd plug at 2660' with 30 sacks, 3rd plug at 40' solid bridge with 15 sacks and 40' solid bridge with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 3:30 a.m. March 15, 1980.

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEDGWICK COUNTY  
 WALLECE-KANSAS  
 MARCH 21 1980

SAMPLE TOPS:

Anhydrite 2700'  
 B/Anhydrite 2735'

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Pearce "D" #1, 430' EL, 2310' NL, Section 28-11S-39W, Wallace County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 25th day of March, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public