


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-199-00026-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Wallace County. Sec. 32 Twp. 11S Rge. 42 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SE/4 SW/4  
Lease Owner States Oil Company  
Lease Name Elizabeth Harold Well No. 1  
Office Address 316 Johnson Building, Shreveport, Louisiana  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 11 19 55  
Application for plugging filed September 11 (by phone) 19 55  
Application for plugging approved September 11 (by phone) 19 55  
Plugging commenced September 11 19 55  
Plugging completed September 11 10:00 P.M. 19 55  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ?  
Producing formation None Depth to top Bottom Total Depth of Well 6020 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
N				13 3/8	296	None
O						
N						
E						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Left hole full of 9.7% mud from 6020' to 270'. 25 sx. cement plug and 1 sack Hulls from 270 to 230. Heavy mud from 230 to 35 feet. 20 sx. cement plug from 35 ft. to surface. Job completed 10:00 P.M. September 11, 1955.

RECEIVED  
STATE CORPORATION COMMISSION  
9-26-1955  
SEP 24 1955  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address Wichita, Kansas

STATE OF LOUISIANA PARISH CADDO  
C. H. Gee COUNTY OF ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Gee  
316 Johnson Building, Shreveport, La.  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 55

My commission expires at death  
John M. Shroy  
Notary Public.

PLUGGING  
FILE SEC 22 T 11 R 22 W  
BOOK PAGE 142 LINE 20

# WELL LOG

15-199-00026-00-00

COMPANY States Oil Company

SEC. 32 T. 11S R. 42W

FARM Harold

NO. 1

LOC. C SE SW


TOTAL DEPTH 6020'

COUNTY Wallace

COMM. August 14, 1955

COMP. September 11, 1955

CONTRACTOR Garvey Drilling Company



CASING 13-3/8" O 277' w/300 sax

ELEVATION Ground 3931

PRODUCTION None

FIGURES INDICATE BOTTOM OF FORMATIONS

## TIGHT HOLE

0-990	shale
990-1290	shale and chalk
1290-1500	shale
1500-1700	shaley sand
1700-2040	shale and sand
2040-2250	sand
2250-2370	shale
2370-2600	sand and shale
2600-2710	shaley sand
2710-2850	anhydrite
2850-3780	sand and shale
3780-3850	lime
3850-4600	lime and streaks shale
4600-4700	sandy lime
4700-4800	lime and shale
4800-4850	lime and chert
4850-5120	lime and shale
5120-5135	shale
5135-5145	sand
5145-5620	lime
5620-5640	limey sand
5640-5990	lime
5990-6020	granite

RECEIVED  
9-26-1955

State of KANSAS }  
County of SEDGWICK } SS :

I, Robert F. White of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Harold #1 well

**PLUGGING**  
FILE SEC 32 T 11 R 42W  
BOOK PAGE 149 LINE 30

Robert F. White  
Attorney in Fact

Subscribed and sworn to before me this 14th day of September 19 55

My Commission Expires: August 8, 1959

Glen Morrison  
NOTARY PUBLIC