

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-143-20,008

LEASE NAME Mildred Stanley

15-143-20008-00-00

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 15 TWP. 12 SRGE. 3 ~~XXXXXX~~(W)

COUNTY Ottawa

Date Well Completed 8-29-90

Plugging Commenced 8-29-90

Plugging Completed _____

LEASE OPERATOR Morris E. Ogle

ADDRESS P. O. Box 992, Casper, WY 82601

PHONE#(307) 237-2227 OPERATORS LICENSE NO. 30434

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-29-90 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom T.D. 3760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8"</u>	<u>218'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 35 sx. cement @ 3733' thru drill pipe.

Spotted 50 sx. cement @ 330' thru drill pipe.

Spotted 25 sx. cement @ 60' thru drill pipe.

Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 448, El Dorado, KS 67042

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1990
9-4-1990
CONSERVATION DIVISION
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Morris E. Ogle

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine


(Address) 401 E. Douglas - Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 90

Carolyn J. Tjaden
Notary Public

My Commission Expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992



15-143-20008-00-00

WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Morris E. Ogle, P. O. Box 992, Casper, WY 82601

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Mildred Stanley Well No. 1

Sec. 15 T. 12S R. 3W Spot C SE SW

County Ottawa State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 218' with 150 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3760'

Drilling Commenced 8-20-90 Drilling Completed 8-29-90

Formation	From	To	Tops
Cellar	0	7	Iatan 2016
Shale	7	740	L/KC 2200
Shale & Lime	740	1285	Cherokee 2700
Shale	1285	1748	Miss 2867
Lime	1748	1845	Kinderhook 3170
Shale - Lime & Sand	1845	1995	Hunton 3310
Shale & Lime	1995	2016	Maquoketa 3440
Lime & Shale	2016	2170	Viola 3544
Shale	2170	2200	Simpson 3648
Lime	2200	2552	Arbuckle 3733
Lime w/ Shale	2552	2600	
Shale & Lime	2600	2700	
Shale	2700	2730	
Shale & Lime	2730	2870	
Lime	2870	3170	
Shale	3170	3310	
Lime	3310	3440	
Shale	3440	3544	
Sand	3554	3760	

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1990

CONSERVATION DIVISION
Wichita, Kansas