

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: High Plains Production, LLC  
Address: 3000 Research Lane, Suite 240 The Woodlands, TX 77380  
Phone: (903) 271-5175 Operator License #: 32390  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4/15/2009 (Date)  
by: Jack McClaskey (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Marmaton Depth to Top: 4216' Bottom: 4320' T.D. \_\_\_\_\_  
Morrow Depth to Top: 5045' Bottom: 5095' T.D. \_\_\_\_\_  
Keyes Depth to Top: 5107' Bottom: 5117' T.D. 5147'

API Number: 15-129-21555-00-00  
Lease Name: Payne  
Well Number: #1-14  
Spot Location (QQQQ): S2 SW - NW - \_\_\_\_\_  
2310 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 14 Twp. 31 S. R. 42  East  West  
County: Morton  
Date Well Completed: 4/24/1998  
Plugging Commenced: 4/16/2009  
Plugging Completed: 4/20/2009

Show depth and thickness of all water, oil and gas formations:

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Marmaton	gas, water	0	1506'	8 5/8"	1506'	0
Morrow	gas, water	0	5179'	5 1/2"	5179'	2028'
Keyes	gas, water					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Mixed 800# hulls & 25sx cement to plug perfs. Shot off and pulled 5 1/2" casing to 1530'. Circulated hole with mud & pumped 50 sx of cement at 1530' to 1390'. Pulled casing, and pumped 40sx of cement at 550' to 430'. Pulled casing and pumped 10sx of cement at 40' to 0'. Cut off 8 5/8" casing 3' below ground level and capped off.

Name of Plugging Contractor: Sargent And Horton Plugging, Inc. License #: 31151 KANSAS CORPORATION COMMISSION  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: High Plains Production, LLC  
State of Kansas County, Finney, ss.  
MAY 14 2009  
RECEIVED

Ron Osterbuhr - Agent (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ron Osterbuhr

(Address) PO Box 1152 Garden City, KS 67846



SUBSCRIBED and SWORN TO before me this 12<sup>th</sup> day of May, 20 09

Gara Jarmer My Commission Expires: 8/27/11  
Notary Public