

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R&B Oil & Gas, Inc.
Address: PO Box 195, Attica, KS 67009
Phone: (620) 254-7251 Operator License #: 31191
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 3800 Bottom: 3810 T.D. 4510

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-095-19051-00-0101
Lease Name: Birkenbaugh Cowwo
Well Number: 21
Spot Location (QQQQ): - SW-SE - NW
2310 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 15 Twp. 29 S. R. 7 East West
County: Kingman
Date Well Completed: 6-8-1964 (spud)
Plugging Commenced: 03-16-09
Plugging Completed: 3-18-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	250	
<u>Kansas City</u>	<u>Oil</u>	<u>3800</u>	<u>3810</u>	<u>5 1/2</u>	<u>4510</u>	<u>2280</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Unhooked well head, raised pole, changed over for rods, pulled rods, changed over for tubing, pulled tubing, sanded off bottom, loaded hole with water, dug cellar, cut nipple out of 5 1/2" casing, set floor, pulled slips, cut surface off 4' below ground, checked hole, sand was at 3750', bailed 5 sacks cement with bailer, ripped casing at 2460', worked pipe, ripped casing at 2280', pipe came free, changed over for casing, pulled casing up to 1100', dug pit, pumped 35 sacks, 100# hulls, pulled casing up to 700', pumped 35 sacks, 100# hulls, pulled up to 300', circulated with 125 sacks to surface, pulled rest of casing tore down rig and floor, emptied pit.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526


KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc. MAY 14 2009

State of Kansas County, Harper, ss.

RECEIVED

R+B Oil + Gas, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Landy Reuberry
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 13th day of May, 20 09

Jane Swingle My Commission Expires: 1-6-2011
Notary Public, Jane Swingle

PKT