

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9855
Name: Grand Mesa Operating Company
Address 1: 1700 N. Waterfront Pkwy, Bldg 600
Address 2: _____
City: Wichita State: KS Zip: 67206 + 5 5 1 4
Contact Person: Ronald N. Sinclair
Phone: (316) 265-3000
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 165-21846-00-00
Spot Description: 90' FNL & 2570' FWL
NE NE NE NW Sec. 20 Twp. 18 S. R. 19 East West
90 Feet from North / South Line of Section
2,570 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rush
Lease Name: Keller Unit Well #: 1-20
Date Well Completed: April 20, 2009
The plugging proposal was approved on: April 16, 2009 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: April 16, 2009
Plugging Completed: April 20, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	1234'	-0-
		Production	5 1/2"	4069'	2230'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled water out of cellar, pumped 30 sxs, 200# hulls down 5 1/2" csg., displaced to 3450', max pressure 1500 PSI, let set 1/2 hr., unpacked casing head, set floor, pulled slips, had 20" stretch, ripped casing @ 2840', 2650', 2410', 2230', pipe came free, pulled casing up to 1260', pumped 15 gel, 50 sxs cement, 100# hulls, pulled to 600', pumped 50 sxs, 100# hulls, pulled to 40', pumped 20 sxs to surface.

KANSAS CORPORATION COMMISSION

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc. **MAY 14 2009**
Address 1: 190 US Highway 56 Address 2: _____ **RECEIVED**
City: Elliwod State: Kansas Zip: 67526 + _____
Phone: (620) 938-2388
Name of Party Responsible for Plugging Fees: Grand Mesa Operating Company
State of Kansas County, Sedgwick, ss.
Ronald N. Sinclair, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] /Ronald N. Sinclair 5/13/09

PST