

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior, Inc.  
Address: PO Box 399 Garden City KS 67846  
Phone: (620) 275-2963 Operator License #: 4058  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas Q&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4-21-09 (Date)  
by: Eric MacLaren (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 6106 Bottom: 6120 T.D. 6205  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-189-20016-0000  
Lease Name: Larrabee  
Well Number: 3 nwne KCC PPT per CP 2/3  
Spot Location (QQQQ): C-SE-SW  
660 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 13 Twp. 32 S. R. 35  East  West  
County: Stevens  
Date Well Completed: APR 1 1968  
Plugging Commenced: 4-27-09  
Plugging Completed: 4-28-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	760	
				4 1/2	6189	1209

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech set CIBP + 2 sx cmt. from 6043 to 6020. Mixed 20 sx plug in 4 1/2 from 1700 to 1440. Shot + pull 4 1/2 to 790. Circ. hole w/mud + mixed 50 sx plug 790 to 640 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731 KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: AMERICAN WARRIOR INC  
State of KS County, Finney, ss.

Kevin Wiles SR (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) P.O. Box 399 Garden City KS 67846

SUBSCRIBED and SWORN TO before me this 13<sup>th</sup> day of May, 20 09  
Mary L. Watts My Commission Expires: 8-7-2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

