

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200, Wichita, KS 67202
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 5/15/09 (Date)
by: Ray Dinkle (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Tarkio Depth to Top: 2101 Bottom: 2104 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-20312-00-00
Lease Name: Hines
Well Number: #1
Spot Location (QQQQ): N2 - N2 - SW -
2310 Feet from North / South Section Line
3960 Feet from East / West Section Line
Sec. 23 Twp. 14 S. R. 11 East West
County: Russell
Date Well Completed: 7/17/1969
Plugging Commenced: 5/15/09
Plugging Completed: 5/15/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	289'	
				4-1/2"	2249'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Klima Well Service MIRU on Hines #1, Perf Tech perf. 4 1/2" casing at 250, 520, 1350 two shots each, tkt # 6590.

RIH with 66 jts. of 2 3/8" tbg. Quality Cementing used 178 sx of 60/40 pozmix with 4% gel and 150#s hulls, tkt.# 3117.

Circ. cement out casing and surface pipe, Pulled tbg. topped off casing with cement RD. KCC Rep. Ray Dinkle.

Plugged and Abandoned.

Name of Plugging Contractor: Klima Well Service License #: 7023

Address: P.O. Box 386, Claflin, KS 67525-0386

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corp

State of Sedgwick County, Kansas, ss.

Gary Sharp

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Gary Sharp

(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 21st day of May 2009

Glenna E. Lowe
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 22 2009

KCC WICHITA

PA