

15-167-22997-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-22,997

LEASE NAME Tobias "A"

WELL NUMBER 1

1,650 Ft. from S Section Line

4,950 Ft. from E Section Line

SEC. 27 TWP. 12 RGE. 13 ~~XX~~ (W)

COUNTY Russell

Date Well Completed 10-15-91

Plugging Commenced 10-16-91

Plugging Completed 10-16-91

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Leroy E. Tobias

ADDRESS HC 69, Box 42, Bunker Hill, KS. 67626

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 3345

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-15-91 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	211'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Spot 25 sax cement @3,367' thru drill pipe. Push bridge plug to 630', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 350', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: LEROY E. TOBIAS

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec. - Treas.

(Employee of contractor) or owner of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 91

Ruth Phillips  
Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1991  
18-23-91  
CONSERVATION DIVISION  
Wichita, Kansas. My Commission Expires:



# Shields


15-167 - 22997 - 00 - 00

Russell, Kansas

## WELL LOG

Operator: Leroy E. Tobias  
 Well: Tobias "A" #1  
 Commenced: October 8, 1991  
 Completed: October 16, 1991  
 Contractor: Shields Drilling Co.

Well Description: SW NW SW  
 Sec. 27-12S-13W  
 Russell Co., Kansas



Elevation: 1,579' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	212'	Cmtd. w/150 sax

### ..... Figures Indicate Bottom of Formations .....

Surface clay & lime streaks	74'
Iron	84'
Sand, shale & hard sand	189'
Shale & sand	596'
Anhydrite	630'
Shale	1,250'
Shale & lime	2,915'
Lime	3,390' RTD

Notes

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-23-91  
 OCT 23 1991  
 CORPORATION DIVISION  
 Wichita, Kansas