

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-003-01681-00-00
NE NE NE Sec/Twp/Rge Sec. 6, T21S, R20E
6055 feet from south section line
47 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS
Name & FEE FUND
Address CHANUTE DISTRICT OFFICE
AB oil well XXXXXXX; Gas Well _____ SWD Well/ Input Well _____

Lease/Well# BOWMAN / BOW43
County ANDERSON
Well Total Depth 650 feet
Production Pipe: 2 Size Feet NA
Surface Casing: 10 Size Feet EST 20
D & A

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, INC. Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KS 66720

Company to plug at: Hour: _____ Day: 27 Month: FEB. 2008

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE, INC. Phone: (620) 431-9212

Were: FILL WELL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received by: _____

Plugging attended by Agent: All XXXXXXX; Part _____ TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: 27 Month: FEB. 2008

Actual Plugging Report: PERFORATE WELL AT 300, 150, AND 75 FEET. RUN 1 INCH INSIDE
2 INCH CASING TO 650 FEET AND PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE
AND TOP OFF WELL. PUMP TOTAL OF 32 SACKS OF CEMENT. WELL PLUGGED.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 10 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONTROL #20070042-043 GPS # BOW43 CONTRACT # 10279
(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Rui Sheng 4/8/08
TECHNICIAN

[Handwritten initials]