

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20466-00-00
Spot: NW Sec/Twnshp/Rge: 13-31S-9E
4348 feet from S Section Line, 4356 feet from E Section Line
Lease Name: WISEMAN Well #: 3
County: ELK Total Vertical Depth: 2313 feet

Operator License No.: 31119

Op Name: WOLFE, ROBERT & DEBBIE S. DBA Lone Wolf Oil

Address: BOX 241
MOLINE, KS 67353

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2008 8:00 AM

Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' PLUG AT 2280', 50' PLUG AT 760' AND 500' TO SURFACE.

75.17

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/26/2008 5:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Filled well with sand and lime chips to 2280'. Ran 5 sacks of cement in with baler at 2280'. Perforated 4.5" casing at 760' and pumped 15 sacks of 60/40 poz-mix with 4% gel and gell spacer to 500'. Shot casing off at 514' and circulated cement to surface. Pulled casing and topped well off. A total of 110 sacks of cement were used to plug this well.

RECEIVED
KCC DISTRICT #3

MAY 19 2009 DAS

CHANUTE, KS

INVOICED

DATE 6-26-09


INV. NO. 2009061625

Remarks:

Plugged through: CSG

District: 03

Signed



(TECHNICIAN)

PRT

RECEIVED

MAY 26 2009

KCC WICHITA