

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20467-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 13-31S-9E
4116 feet from S Section Line, 5213 feet from E Section Line
Lease Name: WISEMAN Well #: 4
County: ELK Total Vertical Depth: 2310 feet

Operator License No.: 31119

Op Name: WOLFE, ROBERT & DEBBIE S. DBA Lone Wolf Oil

Address: BOX 241
MOLINE, KS 67353

75.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2008 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' PLUG AT 1950', 50' PLUG AT 750' AND 500' TO SURFACE.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/26/2008 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Bridge plug at 1950'. Ran 2" to 1950' and pumped 15 sacks of 60/40 poz-mix with 4% gel. Pulled 2" up to 750' and pumped gel spacer. Pulled tubing. Peforated well at 750'. Hooked up to 4.5" casing and pumped 15 more sacks of cement. Shot casing off at 504' and circulated cement to surface. Pulled casing and topped well off. A total of 180 sacks of cement were used to plug this well.

RECEIVED
KCC DISTRICT #3

MAY 19 2009 DAS

CHANUTE, KS

INVOICED
DATE 6-26-09
INV. NO. 2009061625

Remarks:

Plugged through: CSG

District: 03

Signed Qua A Sim
RECEIVED (TECHNICIAN)

MAY 26 2009

KCC WICHITA