

Copy from
LBDMs

3 022937

15-207-19618-00-00
CONTROL NO. 20050019-002

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER NW SW,NE,NE 1/4 Sec/Twp/Rge S28-T.25S.-R.17E.

4606 feet from south section line
1201 feet from east section line

Ø

TECHNICIAN'S PLUGGING REPORT

Operator License # 1D1
Operator: STATE OF KANSAS FeeFund
Name & _____
Address _____

Lease/Well# BENNETT A NO.2 (GPS)
County WOODSON
Well Total Depth 750' feet
Production Pipe: 2" Size Feet 750
Surface Casing: 7" Size Feet 20'
AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC Lic. # 3097
Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: _____ 8 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750" THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN None X

Operations Completed: Hour: 5:30P.M. Day: _____ 8 Month: 11 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 700'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 7" ANNULUS TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 7" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 84 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.2) (THIS WELL WAS NOT ILLUSTRATED ON THE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 21 2005
KCC WICHITA

BW