

4-17-07

15-207-02003-00-00

3 023142

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 19 Month: 3 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD BEEN

CEMENTED IN AT T.D. ONLY. INSIDE THE 4 1/2" CASING WAS APPROX. 1100' OF 2" TUBING

CEMENTED AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE BOTH STRINGS

AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part

TECHNICIAN
None

Operations Completed: Hour: 2:00P.M. Day: 19 Month: 3 2007

Actual Plugging Report: THE 2" AND 4 1/2" CASING WERE PERFORATED AT 700' AND AT 200'.

1" PIPE WAS RAN INTO THE 2" TUBING TO 1080'. CEMENT WAS PUMED INTO THE 1' PIPE

UNTIL CEMENT CIRCULATED FROM INSIDE THE 2" AND FROM THE 2" AND 4 1/2" ANNULUS

AND FROM THE 4 1/2" AND 6" ANNULUS AT SURFACE. DISPLACEMENT WAS FILLED FROM

SURFACE. 220 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (SPOT LOCATION ESTABLISHED BY GPS AS BIS 03)

(If additional description is necessary, use BACK of this form.)

Control #20070029-035

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
KANSAS CORPORATION COMMISSION

APR 16 2007

CONSERVATION DIVISION

PPT