

3 023143

4-17-07
15-207-02006-00-00

To:

API NUMBER ~~20070029-039~~

STATE CORPORATION COMMISSION

SW SE,SW,NE 1/4 Sec/Twp/Rge S.21-T.26S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

2842 feet from south section line

130 S. Market, Room 2078

1657 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

Rose East-Bishop 7
BISHOP NO. 7

Operator License #

100 107

County

WOODSON

Operator: STATE OF KANSAS

Well Total Depth 1100 feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2" Size Feet 1100'

Address

Surface Casing: 6" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 19 Month: 3 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD BEEN

CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2"

CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ PartTECHNICIAN
None

Operations Completed: Hour: 2:00P.M. Day: 19 Month: 3 2007

Actual Plugging Report: THE 4 1/2" CASING WAS PERFORATED AT 700' AND AT 200'

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 825'. CEMENT WAS PUMPED INTO THE

1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AND FROM THE 4 1/2"

AND 6" ANNULUS AT SURFACE. 260 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS BIS 07) Control # 20070029-039
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
KANSAS CORPORATION COMMISSION

APR 16 2007

CONSERVATION DIVISION