


15-063-00004-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Gove County, Sec. 6 Twp. 11S Rge. 26 ~~26~~ (W)

Location as "NE/CNW%SW%" or footage from lines A/C SW/4 SE/4
Lease Owner Barnett Oil Company and R. W. Shields
Lease Name Boone Well No. 1
Office Address 411 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 28, 1959
Application for plugging filed November 28, 1959
Application for plugging approved November 28, 1959
Plugging commenced November 28, 1959
Plugging completed November 28, 1959
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	209 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed first plug to 600'; spotted 20 sacks of cement through drill pipe; filled hole to 170' with mud. Pushed second plug to 170' with 1/2 sack of hulls on top and filled with 20 sacks of cement to 100'. Well left open above the fresh water protecting bridge set at 170' to 100', to be used as a fresh water well. Authorization signed by James D. Boone, Landowner; witnessed by Gilbert P. Leiker, Conservation Agent.

Plugged rat hole with 5 sacks of cement.

(Well Log attached)

RECEIVED
STATE CORPORATION COMMISSION
12-01-1959
DEC 4 1959

CONSERVATION DIVISION
Wichita

Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey (employee of ~~owner~~ or ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1959

My commission expires February 27, 1960.

Mildred F. Willis
Notary Public.

15-063-00004-00-00

BARNETT OIL COMPANY and R. W. SHIELDS
WELL LOG - BOONE WELL NO. 1
A/C SW/4 SE/4 SECTION 6-11S-26W
GOVE COUNTY, KANSAS

Date Commenced: 11-20-59
Date Completed: 11-28-59

<u>From</u>	<u>To</u>	<u>Formation</u>
0	60	Surface Clay
60	110	Sand
110	1250	Shale and shells
1250	1295	Shale and sand
1295	1530	Shale and shells
1530	1585	Sand
1585	1910	Shale and shells
1910	2168	Shale and sand
2168	2198	Shaley Red Bed
2198	2230	Anhydrite
2230	2350	Shale and shells
2350	2485	Shale and lime shell
2485	2645	Shale and shells
2645	3520	Shale and lime
3520	3607	Lime and shale
3607	3695	Shale and lime
3695	3880	Lime and shale
3880	4165	Lime
4165	4170	Lime and shale (T.D.) (D. & A.)

RECEIVED
STATE CONSERVATION COMMISSION
DEC 4 1959

CONSERVATION DIVISION
Wichita, Kansas

12-04-1959

Set 8 5/8", 28# s.s. casing @ 209 1/2'
with 200 sacks of H.A. 5 cement.

A F F I D A V I T


STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

I, F. H. Rousey, Office Manager of the Barnett Oil Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

F. H. Rousey

Subscribed and sworn to before me this 3rd day of December,

Mildred F. Willis
Notary Public



My Commission expires: February 27, 1960.