


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Gove County, Sec. 12 Twp. 11S Rge. 26 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NW



Locate well correctly on above
Section Plot

Lease Owner Associates Oil & Gas
Lease Name Maxwell Well No. 1
Office Address 501 One Twenty Building, Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed 2/17/78 19
Application for plugging filed 2/17/78 19
Application for plugging approved 2/17/78 19
Plugging commenced 2/17/78 19
Plugging completed 2/17/78 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4080
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	265	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug at 1000' with 70 sacks 50/50 Poz, 6% gel
Middle Plug at 240' with 20 sacks 50/50 Poz, 6% gel
Top & Bridge at 40' with 10 sacks 50/50 Poz, 6% gel
2 sacks in rathole
Job complete 3 p.m. 2/17/78

RECEIVED
FEB 28 1978
02-28-1978
STATE CORPORATION COMMISSION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita, 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of February, 1978

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



15-153-20369-00-00

DRILLERS LOG

OPERATOR: Associates Oil & Gas
 501 One Twenty Building
 Wichita, Kansas 67202

LEASE: Maxwell No. 1
 SE NW NW Sec. 12-11S-26W
 Gove County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 2/10/78

COMPLETED: 2/17/78

RTD: 4080'

CASING: 8-5/8" set at 265' with 175 sx

0' to 268' 12 1/4" Surface Hole Clay & Shale
 268' to 1608' Shale
 1608' to 1700' Shale & Shells
 1700' to 1883' Sane
 1883' to 2110' Shale & Shells
 2110' to 2150' Anhydrite
 2150' to 2455' Shale & Shells
 2455' to 3140' Shale & Lime
 3140' to 3905' Lime & Shale
 3905' to 4080' Lime
 RTD 4080'

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 28 1978
 02-28-1978
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg of the Slawson Drilling Company, Inc.
 hereby state that the above and foregoing is a true and accurate copy of
 the log of the Maxwell No.1 well.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this 25th day of February, 1978

Mary Lou Taylor
 Mary Lou Taylor

My commission expires January 17, 1981

