

15-109-20241-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Logan SEC. 23 TWP. 11S RGE. 32W E/W
Location as in quarters or footage from lines:
SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner George R. Jones
Lease Name KURTZ Well No. 1
Office Address 125 N. Market, Suite #1210, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7/01/82
Application for plugging filed 7/01/82
Plugging commenced 7/01/82
Plugging completed 7/01/82

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation _____ Depth to top _____ bottom T.D. 4625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Set 1st plug @ 1600' with 100 sx.
Set 2nd plug @ 300' with 40 sx.
Set 3rd plug @ 40' Sol. Bridge with 10 sx.
10 sx. in Rathole. 50-50 posmix, 4% gel, 1% c.c.
State plugger Carl Goodrow.
Plug was down @ 10:00 a.m., 7/01/82

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Ass. Sec/Treas (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 82

My Commission expires: 7-13-85

Elizabeth G. Terry Notary Public
STATE CORPORATION COMMISSION
07-16-1982
JUL 16 1982
RECEIVED
NOTARY PUBLIC
STATE OF KANSAS
ELIZABETH G. TERRY
Wichita, Kansas
CONSERVATION DIVISION
Wichita, Kansas

15- ~~109~~ ¹⁰⁹ ~~20241~~ ²⁰²⁴¹ -00-00

CONTRACTORS WELL LOG

JUL 23 1982

OPERATOR: George R. Jones
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KURTZ #1
 LOCATION: SW NW, Sec. 23-11S-32W
 Logan County, Kansas
 SPUD DATE: 6/21/82
 COMPLETION DATE: 7/01/82
 API No.: 15-109-20,241

0	284	Shale & Sand
284	536	Sand & Shale
536	2030	Shale & Sand
2030	2785	Shale
2785	3150	Sand & Shale
3150	3345	Shale & Lime
3345	4139	Lime & Shale
4139	4275	Lime
4275	4447	Lime & Shale
4447	4625	Shale & Lime
	4625	Rotary Total Depth

Spud hole @ 6/21/82. Drilled 285' of a 12 1/2" hole. Ran 7 jts. of 8 5/8" 20# casing (tally 274.76') set @ 281.76' and cemented with 200 sx. Common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 4:45 a.m., 6/22/82.

4625' TD. Set 1st plug @ 1600' with 100 sx. Set 2nd plug @ 300' with 40 sx. Set 3rd plug @ 40' Sol. Bridge with 10 sx. 10 sx. in Rathole. 50-50 posmix, 4% gel, 1% c.c. Plug was down @ 10:00 a.m., 7/01/82. State plugger Carl Goodrow.

SAMPLE TOPS:

Anhydrite 2597'
 B/Anhyd. 2646'

RECEIVED
 STATE CORPORATION COMMISSION
 07-27-1982
 JUL 27 1982
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack K. Wharton, Ass. Sec./Treas. of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KURTZ #1, SW NW, Sec. 23-11S-32W, Logan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack K. Wharton
 Jack K. Wharton, Ass. Sec./Tre

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 21st day of July, 1982.

Elizabeth G. Terry
 Elizabeth G. Terry
 Notary Public

my commission expires 7-13-85

