

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER. 15-109-20,427-00-00

LEASE NAME Engle

WELL NUMBER 1

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 25 TWP. 11 RGE. 32 (XXX) (W)

COUNTY Logan

Date Well Completed 11-20-86

Plugging Commenced 11-20-86

Plugging Completed 11-20-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 801 Union Center, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6, State plugger, Marion Schmidt

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	329	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump heavy mud to 2530'-2430', 25 sacks; pump heavy mud to 1600'-1200', 100 sacks plus 1 sack celoflake;
pump heavy mud to 360'-200', 40 sacks; pump heavy mud to 40' to solid bridge, 10 sacks; 15 sacks in the rathole; 10 sacks in the mousehole; all cement 60/40 posmix, 6% gel, 3% ca. cl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Secy/Treas.

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 87

Clarice M. Mize
Clarice M. Mize Notary Public

My Commission Expires: November 28, 1988



01-07-1987
JAN 7 1987
Form CP-4
CONSERVED 01-07-86
Wichita, Kansas