

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-109-20068-00-01

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Logan SEC. 30 TWP. 11s RGE. 32w E/W
 Location as in quarters or footage from lines:
 SW NW SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner A. Scott Ritchie
 Lease Name Ehrlick #1 Well No. _____
 Office Address 125 N. Market, Suite 950, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 1/13/83
 Plugging completed 1/17/83
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation _____ Depth to top _____ bottom _____ T.D. 4785'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	293'	none
				4 1/2"	4526'	1536'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Squeezed 4 1/2" casing with 2 sacks hulls, 12 sacks gel, 50 sacks cement.

Released plug & displaced to 2200'. Shot at 2005', 1810', & 1530'.

Pulled total of 49 joints. Squeezed hole with 2 sacks hulls, 5 sacks gel,
 100 sacks cement, & 25 sacks gel. Released plug & displaced with 70 sacks
 cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January 1983



My Commission expires:

Irene Hoover
 Notary Public.
 STATE CORPORATION COMMISSION
 RECEIVE
 JAN 24 1983
 CONSERVATION
 01-24-1983
 Wichita