

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-063-20,888-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F & M OIL CO., INC. OPERATORS LICENSE NO. 5313

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE-# (316) 262-2636

LEASE (FARM) Reinecker "B" WELL NO. 1 WELL LOCATION NE SW SW COUNTY Gove

SEC. 20 TWP. 11S RGE. 26W ~~12E~~ or (W) TOTAL DEPTH 4590' PLUG BACK TD -----

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A XX SWD or INJ WELL \_\_\_\_\_ DOCKET NO. (CL)

SURFACE CASING SIZE 8-5/8" SET AT 309' CEMENTED WITH 200 SACKS

CASING SIZE ----- SET AT --- CEMENTED WITH ---- SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 1st plug @ 2270' w/25 sxs, 2nd plug @

1370' w/100 sxs & 1 sx flo-cel, 3rd plug @ 330' w/40 sxs, 4th plug @ 40' w/10 sxs, 10 sxs in

rat hole, cmt. by Sun w/50/50 poz, 6% gel, 3% CC, plug down @ 1:30 AM 3-16-85.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not required IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 16, 1985 1:30 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: MAR 22 1985

Lyle Cason PHONE # (316) 596-2140

ADDRESS Rt. #1, Langdon, Ks. 67549

PLUGGING CONTRACTOR Union Drilling Co., Inc. LICENSE NO. 5103

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE # (316) 262-1872

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]

(Operator or Agent)

DATE: March 20, 1985