

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-23232-00-00

LEASE NAME Steckel Trust

WELL NUMBER 2

1,190 Ft. from ^N Section Line

1,100 Ft. from ^W Section Line

SEC. 16 TWP. 12S RGE. 14 (E) or (W)

COUNTY Russell

Date Well Completed 8-17-03

Plugging Commenced 8-17-03

Plugging Completed 8-17-03

LEASE OPERATOR Double Eagle Exploration, Inc.

ADDRESS 221 S. Broadway, STE 310, Wichita, KS 67202

PHONE (316) 264-0422 OPERATORS LICENSE NO. 6009

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-17-03 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	431'	Cmtd. w/250 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Push bridge plug to 3,224', pump 25 sax cement on plug thru drill pipe, push bridge plug to 820', pump 25 sax cement on plug thru drill pipe, push bridge plug to 470', pump 60 sax cement on plug, push wiper plug to 40', dump 10 sax cement on plug to cellar, dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Double Eagle Exploration, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Jack P Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 20th day of August, 2003

Ruth Phillips
Notary Public

My Commission Expires: _____

