


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 20 Twp. 12S Rge. 14 (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines. NW NW SW  
Lease Owner Jay Bergman Oil Company  
Lease Name Kaug Well No. 1  
Office Address 425 Union Center Bldg. Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 20 19 62  
Application for plugging filed June 20 19 62  
Application for plugging approved June 20 19 62  
Plugging commenced June 20 19 62  
Plugging completed June 20 19 62  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 400 feet, set plug  
with sack hulls on top 20  
sacks cement. Mud to 40 feet,  
set plug, dump 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1962  
06-28-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bergman Oil Company 507  
Address 425 Union Center Bldg. Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
Harold Bergman, Manager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman  
425 Union Center Bldg. Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 62

My commission expires August 2, 1962

Donna Johnson  
Notary Public.



WELL LOG

KRUG #1  
 NW NW SW SECTION 20-12S-14W,  
 RUSSELL COUNTY, KANSAS

DATE COMMENCED: JUNE 12, 1962  
 DATE COMPLETED: JUNE 20, 1962  
 ELEVATION: 1611 KB

0	-	180	SAND AND SILT
180	-	295	DAKOTA SAND
295	-	430	SHALE AND SHELLS
430	-	684	RED BED
684	-	689	ANHYDRITE
689	-	700	ANHYDRITE
700	-	720	ANHYDRITE
720	-	1320	SHALE
1320	-	1380	SHALE AND SHELLS
1380	-	1570	LIME AND SHALE
1570	-	1740	LIME AND SHALE
1740	-	1845	SHALE AND LIME
1845	-	1985	SHALE AND LIME
1985	-	2185	SHALE AND LIME
2185	-	2350	LIME AND SHALE
2350	-	2515	SHALE AND LIME
2515	-	2560	LIME AND SHALE
2560	-	2620	LIME
2620	-	2725	LIME
2725	-	2800	LIME
2800	-	2837	LIME
2837	-	2841	LIME
2841	-	2880	LIME
2880	-	2917	LIME AND CHERT
2917	-	2975	LIME
2975	-	2980	LIME
2980	-	3014	LIME
3014	-	3065	LIME
3065	-	3105	LIME
3105	-	3126	LIME - ARBUCKLE
3126			ROTARY TOTAL DEPTH

TOPS:  
 HEEBNER 2737  
 TORONTO 2757  
 LANSING 2790  
 ARBUCKLE 3096

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUN 28 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS     )  
                           )     SS.  
 COUNTY OF SEDGWICK )

I, DO SWEAR THAT THE STATEMENTS AND MATTER HEREIN CONTAINED ARE TRUE TO THE BEST OF MY KNOWLEDGE.

*Harold Bergman*  
 HAROLD BERGMAN

SUBSCRIBED AND SWORN TO BEFORE ME THIS 27TH DAY OF JUNE, 1962.

*Norma J. Johnson*  
 NORMA J. JOHNSON, NOTARY PUBLIC

MY COMMISSION EXPIRES:  
 AUGUST 2, 1962