


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Russell County, Sec. 22 Twp. 12 Rge. (E) 14 (W) SW:NE

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines _____
Lease Owner Franco Central Oil Company
Lease Name Kartman Well No. #1
Office Address Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 10 19 50
Application for plugging filed August 26 19 54
Application for plugging approved August 27 19 54
Plugging commenced September 7 19 54
Plugging completed September 7 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Warren H. Horner

Producing formation Kansas City Lime Depth to top 3008 Bottom 3010 Total Depth of Well 3278 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City Lime	Oil	3008	3010	5 1/2	3276'	2,570'
Arbuckle	Water	3274	3278	8-5/8	224	No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 2990'. Dumped 5 sks cement to 2950'. Pulled pipe filled hole with mud to 220'. Put in 10' rock bridge to 210'. Mixed and run 20 sks cement to 150'. Filled hole with mud from 150' to 35'. Put in 5' rock bridge to 30'. Mixed and run 10 sks cement filled to top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Casing Pulling Co.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. M. Clothier (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. M. Clothier*

512 Fourth National Bank Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 54

My commission expires 10-21-57

24-7368-5 3-53-20M

PLUGGING
ALL 22 T12 R 14W
BOOK PAGE 59 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1954
CONSERVATION DIVISION
Wichita, Kansas

Notary Public.

COMPANY: Franco Central Oil Company
 CONTRACTOR: Mallard Drilling Company
 FARM: Kortman #1
 LOCATION: SWE 3/4 NE/4 Sec. 22-12S-14W
 Russell County, Kansas
 COMMENCED: February 20, 1950--rotary
 COMPLETED: March 2, 1950--rotary

0	to	223	Shale and shells
223	to	580	Shale and shells
580	to	915	Shale, lime and sand
915	to	1495	Shale and shells
1495	to	1685	Shale and lime
1685	to	1950	Lime
1950	to	2065	Lime and shale
2065	to	2235	Shale and lime
2235	to	2425	Shale and lime
2425	to	2550	Shale and lime
2550	to	2670	Shale and lime
2670	to	2805	Lime
2805	to	2885	Lime
2885	to	2985	Lime
2985	to	3070	Lime
3070	to	3184	Lime
3184	to	3260	Lime
3260	to	3275	Conglomerate
3275	to	3278	Arbuckle
		3278	L.P. Rotary

Set 224 feet of 8 5/8" surface pipe. Cemented with 150 sacks cement.

Set 5 1/2" pipe at 3274. Cemented with 150 sacks cement.

TOPS: Arbuckle 3273.

Measurements taken from derrick floor

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Kortman #1, Russell County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 7th day of March 1950.

James W. [Signature]

My commission expires 12/4/57

PLUGGING
 FILE NO. 22-12S-14W
 BOOK PAGE 59 LINE 25