

15-167-04970-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD


Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Russell County. Sec. 22 Twp 12 Rge 14 ~~23~~ (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE SE NW
Lease Owner Franco Central Oil Company
Lease Name Lewis Well No. 1
Office Address 306 4th National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 28, 1950
Application for plugging filed July 26, 1950
Application for plugging approved July 28, 1950
Plugging commenced August 1, 1950
Plugging completed August 5, 1950
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3198 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
KC Ls	Water	3070	3078	8 5/8	217'	No
KC Ls	Water	3012	3014	5 1/2	2161'	2518'
KC Ls	Water	2996	3000			
KC Ls	Water	2970	2976			
KC Ls	Water	2936	2942			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with chat from 2956 to 2925 - dumped 4 sacks cement filled to 2900.
Shot pipe off at 2500' - pulled some - filled hole with mud to 215'. Bridged with
rock from 215' to 210'. Run 15 sacks cement filled up to 180' - filled hole with
mud from 180' to 40'. Bridged with rock from 40' to 35' - filled hole to top with
cement.

08-22-50
AUG 22 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. M. Clothier

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August, 1950.

Notary Public.

My commission expires

3-9-51



COMPANY: FRANCO CENTRAL OIL COMPANY Rotary Drilling Commenced: 4-23-50
306 Fourth National Bank Bldg. Rotary Drilling Completed: 4-30-50
Wichita, Kansas

LOCATION: LEWIS #1
SE SE NW Sec. 22-128-14W
Russell County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY, INC.
Wichita, Kansas

CASING RECORD: 217' (7 jts.) 8 5/8" surface casing set at 217' in a 12 1/2" hole,
cemented with 150 sacks cement.
3164' (98 jts.) 5 1/2" casing set at 3164' in a 7 7/8" hole, cemented
with 150 sacks cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Cellar	5	Circulate for samples at 2888'.
Sand	30	" " " " 2982'.
Shale & Shells	220	" " " " 3000'.
Shale	390	" " " " 3015'.
Sand	455	" " " " 3073'.
Shale & Sand	575	
Shale & Red Bed	850	Slope test at 1000' - 00 off.
Red Bed, Shale & shells	1350	" " " 2000' - 00 off.
Shale & Lime	1575	" " " 2975' - 00 off.
Lime	2190	S.L.M. at 2975' - O.K.
Lime & Shale	2435	
Shale	2590	
Shale & Lime	2887	Lost Circulation at 2711'.
Lime	3164 Rotary T.D.	" " " 3152'.

The undersigned, C. W. Sebitts, Secretary of PICKRELL DRILLING COMPANY, INC., hereby certifies in behalf of said corporation, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY, INC.
By [Signature]
Secretary

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BE IT REMEMBERED that on this 8th day of May, 1950, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came C. W. Sebitts, Secretary of Pickrell Drilling Company, Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

[Signature]
Notary Public

My commission expires January 28, 1953.

PLUGGING
FILE SEC 22-128-14W
BOOK PAGE 17 LINE 24