

15-167-04774-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

*Rec'd
KCC
08-02-50*

WELL PLUGGING RECORD

Russell County, Sec. 22 Twp 12S Rge. 14W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE

Lease Owner Gough W. Davis

Lease Name Wagner Well No. 1

Office Address 301 S. Clifton, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 4, 1950 19

Application for plugging filed July 24, 1950 (verbal) 19

Application for plugging approved July 24, 1950 (verbal) 19

Plugging commenced July 24, 1950 19

Plugging completed July 30, 1950 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3276 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	254'	
				5-1/2"	3275	2542'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8-5/8" at 254 feet circulated with cement.
5-1/2" set at 3275 feet with 135 sacks of cement behind. Lane-wells plugs and cement to 3000 feet. Top perforations at 2960 feet, filled with chat to 2950 feet. Set 4 sacks cement with dump bailer, pulled 2542 feet of 5-1/2", filled hole with heavy mud to 250 feet. Set rock to 240 feet. Set 15 sacks of cement, filled with mud to 40 feet. Set rock bridge and 10 sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Well Servicing Co.,

Address 9th & Kansas, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, Gough W. Davis (employee of owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gough W. Davis

301 S. Clifton, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1953

Seward S. Greider Notary Public.

My commission expires January 31, 1957

PLUGGING
FILE SEC 22 T 12 R 14W
BOOK PAGE 19 LINE 14

DRILLER'S LOG

Company: Gough W. Davis

Sec. 22 Twp. 12 Rge. 14W
NW NW SE

Farm: Wagner Well No. 1

Total Depth: 3276'

County: Russell,
Kansas

Comm.: 3-24-50 Comp.: 4-4-50

Contractor: Glenn Peel Drilling Co., Inc.

Elevation:

Casing:

Production:

8 5/8" 254' cem.
5 1/2" 3275' cem.

Figures below indicate bottom of formations

Surface Clay	0 -	20
Sand		40
Shale, Shell & Sand		100
Shale		255
Red Bed, Shale		375
Sand		420
Shale & Shells		470
Shale, Shells & Lime		790
Shale, Shells & Pyrite		835
Anhydrite		875
Shale & Shells		1215
Shale & Salt		1350
Shale & Lime		1830
Lime		2050
Lime & Shale		2108
Shale & Lime		2495
Lime & Shale		2690
Lime		3276
Total Depth		3276

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: Way Herber

SUBSCRIBED AND SWORN to before me this 8th day of September, 1950

My commission expires June 4, 1951

Marian M. Herber
Notary Public