



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-063-20089-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1971
CONSERVATION DIVISION
Wichita, Kansas
10-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Pacific Oil & Gas Company,

Complete Address: Colcord Building, Oklahoma City, Oklahoma.

Lease Name: Inlec Well No. 1

Location: CNE-NE Sec. 10 Twp. 11 Rge. (E)(W) 26

County: Gove Total Depth 4098' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

305'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.
cement thru DP. Pull DP to 340' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent