



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

10-06-1969

15-063-20042-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsey of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Lindsey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Flora Well No. C-1

Location: 660' FNL & 560' FEL Sec. 3 Twp. 11 Rge. (E)(W) 26

County: Gove Total Depth 4630 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lindsey was instructed to plug the well as follows:

357'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota Section @ 1118'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.  
cement thru DP. Pull DP to 390' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent