

SIDE TWO

15-167-21934-00-00

ACO-1 WELL HISTORY

OPERATOR Rains & Williamson Oil Co., LEASE Tepee #1 SEC. 33 TWP. 12 SRGE. 14W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2786-2812, 30 (30) 60 (30). Rec. 30' Gsy. Sl. oil spkd. mud, 180' Gsy. mud. FP's 48-68, 87-107. FBHP 583.			<u>E. LOG TOPS</u>	
DST #2 - 2816-2824, 30 (30) 60 (30). Rec. 60' GIP, 60' Gsy. Sl. OCM, 60' Gsy. oil spkd. mud. FP's 48-48, 58-68, IBHP 679, FBHP 660.			Anhydrite	640 (+958)
			Topeka	2503 (-905)
			Heebner	2727 (-1129)
			Lansing	2783 (-1185)
			BKC	3045 (-1447)
			Arbuckle	3104 (-1506)
			LTD	3121 (-1523)
DST #3 - 2938-2972, 30 (30) 30 (30). Rec. 5' mud. FP's 58-58, 67-67. IBHP 67, FBHP 67.				

*Revd
JULY 7-1982*

RELEASED
JUL 01 1982
FROM CONFIDENTIAL

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	14 3/4"	13 3/8"	34#	77'	Common	50 sx.	3% cc., 2% gel.
Surface	12 1/4"	8 5/8"	24#	645'	60/40 poz. Common	200 sx. 125 sx.	3% cc., 2% gel. 3% cc., 2% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
--------------------------	---	---------

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water %	Gas-oil ratio
---------------------------------	-----	-----	---------	---------------

Disposition of gas (vented, used on lease or sold)	Perforations
--	--------------