

15-109-20052-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Logan County, Sec 32 Twp 11S Rge. 32W (E) (W)
Location as "NE/CNW&SW" or footage from lines C SE SW
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter
Lease Name Holmberg Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed January 5, 1976 19
Application for plugging filed January 5, 1976 19
Application for plugging approved January 5, 1976 19
Plugging commenced January 5, 1976 19
Plugging completed January 5, 1976 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4703 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	257'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1500' w/70 sacks cement
Plugged through drill pipe @ 240' w/20 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

JAN 7 1976
01-07-1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1976

My commission expires

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard Notary Public.

WELL LOG

15-109-20052-00-00

CHIEF DRILLING CO., INC. & BILL J. PORTER
905 Century Plaza
Wichita, Kansas 67202

#1 HOLMBERG
C SE SW Sec. 32-11S-32W
Logan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Ran 251' (7 Jts.) 8 5/8", set @ 257'
cemented w/170 sx. common quick set.

COMMENCED: 12/18/75
COMPLETED: 1/5/76

FORMATION	FROM	TO	ELEVATIONS
Shale & Sand	0	261	3058 Gr.
Sand & Shale	261	1420	3061 D.F.
Shale	1420	2377	3063 K.B.
Shale & Sand	2377	2798	
Shale	2798	3062	
Lime	3062	4703	
Total Depth	4703		

FORMATION TOPS	LOG TOPS:
Anhydrite	2592 + 471
Base Anhydrite	2618 + 445
Heebner	4023 - 960
Toronto	4051 - 988
Lansing	4068 - 1005
Base K. C.	4352 - 1289
Marmaton	4389 - 1326
Ft. Scott	4541 - 1478
Cherokee	4565 - 1502
Miss.	4655 - 1592
Log TD	4703 - 1640

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1976
01-07-1976
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SE SW Section 32-11S-32W Logan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 6th day of January, 1976.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard - Notary Public