

STATE OF KANSAS
CORPORATION COMMISSION
Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20-404 ~~00-00~~

LEASE NAME ELLEGOOD

WELL NUMBER #34-1

NE NE NE
SPOT LOCATION 34-11S-32W

SEC. 34 TWP. 11 RGE. 32 (W)

COUNTY Logan

Date Well Completed 10-26-85

Plugging Commenced 10-26-85

Plugging Completed 10-26-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

OPERATOR Chief Drilling Co., Inc.

ADDRESS 905 Century Plaza, Wichita, Ks. 67202

PHONE (316) 262-3791 OPERATORS LICENSE NO. 9835

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Do you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 Hays

ACQ-1 filed? yes If not, is well log attached? yes

Producing formation NA Depth to top _____ bottom T.O. 4750'

Give depth and thickness of all water, oil and gas formations.

GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	8 5/8"	293' set @	296'	cem. w/175		sk. 60-40 posmix, 3% gel 2% cc

Describe in detail the manner in which the well was plugged, indicating where mud fluid was placed and the method or methods used in introducing it into hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged w/180 sks. 60-40 posmix, 6% gel, 3% cc 1 bag of flow seal 1st plug @ 2600' w/20 sks. 2nd plug @ 1625' w/100 sks. & 1 sk. flow seal, 3rd plug @ 350' w/40 sks. 4th plug solid bridge plug @ 40' w/10 sks. 10 sks in BH State Pluggor Gih Scheek Hays Dist. # 6 9:30 am 11:30 am
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. Rig # 1 License No. 5883
Address 905 Century Plaza, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr. (employee of operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F.W. Shelton, Jr.
(Address) 905 Century Plaza, Wichita, Ks. 67202

MARTHA E. GUSTIN
SUBSCRIBED AND SWORN TO before me this 28 day of Oct., 19 85
STATE OF KANSAS
NOTARY PUBLIC EXPIRES 4-15-89

Martha E. Gustin
Notary Public

Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1985
12-19-1985
CONSERVATION DIVISION
WICHITA, KANSAS

15-109- 20404-00-00

WELL LOG

ELLEGOOD #34-1
NE NE NE 34-11S-32W
LOGAN COUNTY, KS.

OPERATOR: L.B. PETROLEUM, INC.
CONTRACTOR: WARRIOR DRILLING CO. RIG #1
COMMENCED: 10-16-85
COMPLETED: 10-26-85


8 5/8" @ 296' w/175 sx. 60-40 posmix
3% gel, 2% cc

0	55	Surface clay
55	364	clay & sand
364	2583	shale
2583	2607	Anhydrite
2607	3214	Shale
3214	4567	shale/lime.
4567	4750	lime
4750'		RTD

D & A Plugged

We certify that the above and foregoing is a true and correct copy of the log on the #34-1 Ellegood, located in Logan County, Ks.


WARRIOR DRILLING CO.



F.W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 28th day of October, 1985.

MARATHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 4-15-89



Martha E. Gustin, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1985
CONSERVATION DIVISION