


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-167-00283-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 35 Twp. 12 Rge. 14 (E) W. (W)

Location as "NE/CNWSW" or footage from lines NW/NW/NW/

Lease Owner Louis M. Mai

Lease Name Mai-Woelk No 1 Well No. _____

Office Address Russell, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced June 20 19 55

Plugging completed July 12 19 55

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Milton Galliard

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2916 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 2916 feet to surface, feet for each plug set.

Hole plugged back from 2916 to 2897 with cement plug- Hole filled with sand from 2897 to 2832; five sacks of cement placed in hole with dump bailer to form cement plug from 2832 to 2792; Halliburton pump trucks pumped in 20 sacks of mud and 100 sacks of cement under pressure to cement hole to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co

Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.
Louis M. Mai (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louis M. Mai

(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of July, 19 55

My commission expires 8-9-1958.

Betty Jean Galyard
Notary Public.

PLUGGING
FILE SEC 35 T 12 R 14W
BOOK PAGE 126 LINE 42

07-18-1955
Wichita, Kansas

Louis M. Mai

15-167-00283 - 00 - 00

OPERATOR: ~~R. P. Nixon~~
Russell, Kansas

CONTRACTOR: MAST DRILLING, INC.
Russell, Kansas

LEASE: well #1
SW NW NW/4 of
NW/4 of 35-12-14
Russell County, Ks.

COMMENCED: 3-7-55

COMPLETED: 3-15-55

<u>FORMATION</u>	<u>DEPTH</u>
Clay	25
Rock	72
Shale	115
Sand	140
Shale &-Blue & Shells	206
Shale & Shells	309
Pyrite	340
Shale & Shells	520
Shale - Red Rock	553
Red Bed	670
Red Bed	699
Anhydrite	730
Shale Shells	920
Shale-Shells-Salt	1265
Shale & Lime	1630
Lime	1715
Lime & Shale	2185
Shale	2385
Shale-Lime-Sand	2492
Shale & Lime	2585
Lime	2920
TOTAL DEPTH	2920

I hereby certify that the above is true and correct to the best of my knowledge.

Louis M. Mai

STATE OF KANSAS)
)
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 14th day of June, 1955.

Betty Jean Galyardt
Notary Public

My Commission expires 8-9-58

35-12-14
26 42

06-15-1955