

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Russell County, Sec. 2 Twp. 12 Rge. 15 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Anschutz Drilling Company, Inc.

Lease Name C. Shaffer Well No. 1

Office Address Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-8 19 52

Application for plugging filed 11-8 19 52

Application for plugging approved 11-8 19 52

Plugging commenced 11-8 19 52

Plugging completed 11-8 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3261 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	120'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 20' with 5 sacks cement
Bottom plug set at 125 feet with 20 sacks cement

STATE CORPORATION COMMISSION
NOV 13 1952
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Company, Inc.
Address Union National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler
Union Nat'l Bk Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 52

Notary Public. Jacqueline K...

My commission expires May 2, 1956

PLUGGING
FILE SEC 2 T 12 R 15
BOOK PAGE 58 LINE 2

15-167-04782-00-00

DRILLER'S LOG

Anschutz Drilling Company, Inc.
#1 C. Shaffer
NW NW SE - 2-12S-15W
Russell County, Kansas

<u>FROM</u>	<u>TO</u>	
0	140	Shale
140	320	Shale & red bed
320	405	Sand
405	817	Red bed & shale
817	855	Anhydrite
855	1500	Shale & shells
1500	1855	Lime
1855	2185	Shale & lime
2185	2200	Lime
2200	2330	Shale
2330	2500	Shale & lime streaks
2500	2600	Shale
2600	2715	Lime
2715	2765	Lime & shale
2765	2829	Lime
2829	2832	Heebner shale
2832	3200	Lime
3200	3230	Shale
3230	3248	Arbuckle
3248	3261	Lime

COMMENCED: 10-27-52
COMPLETED: 11-8-52

CASING RECORD

Set 8-5/8" surface casing at 120 feet with 100 sacks cement.

ELEVATION: 1761 RB

TOPS

Anhydrite 815
Topeka 2822
Heebner 2873
Toronto 2894
Lansing 2926
Arbuckle 3234

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log on the #1 C. Shaffer well, located NW NW SE of Section 2-12S-15W, Russell County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *Leon L. Mehler*
Leon L. Mehler

Subscribed and sworn to before me this 12th day of November, 1952.

Jacqueline Linn
Notary Public

My Commission Expires: May 2, 1956

RECEIVED
REGISTRATION COMMISSION
NOV 13 1952
11-13-1952

PLUGGING
FILE SEC 2 T 12 R 152
BOOK PAGE 58 LINE 8