


15-167-00264-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Russell County. Sec. 2 Twp. 12 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/SW
Lease Owner Chet Loving
Lease Name Shaeffer Well No. B-1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 7-29 19 57
Plugging completed _____ 8-4 19 57
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Milton Galyardt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3142' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,375'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 3142'.
Plugging started 7-29-57. Finished 8-4-57.
Plugged off bottom with sand to 2800' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 2,375'. Pulled pipe out of hole and plugged well with mud to 300' and set permanent rockbridge. Dumped 20 sacks cement. Filled hole with mdd to 35' and mixed 10 sacks for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 57
Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC. 2 T. 12 R. 15W
BOOK PAGE 28 LINE 13

AUG 8 1957
08-08-1957
WICHITA, KANSAS

WELL LOG

COMPANY Chester Loving
 CONTRACTOR S & W Drilling Co.
 FARM Shaffer 'B' #1
 LOCATION SW SW SW of 2-12-15W
 Russell County, Kansas
 ELEVATION 1658 KB
 SURFACE CASING 8 5/8" cemented at 714' w/400 Pozmix, 1% CC
 COMMENCED June 1, 1957
 COMPLETED June 11, 1957

Formation	Depth
Surface clay, sand & shale	70
Shale, shells & pyrite	326
Shale, shells & sand	460
Red bed, shale & chalk	708
Anhydrite	740
Shale and shells	1505
Broken Lime	1900
Lime and shale	2585
Lime	2870
Lime	3050
Lime and shale	3113
Arbuckle	3123
Rotary total depth	3123

TCPS

Anhydrite 708 (✓ 950)
 Arbuckle 3113 (-1455)

A E E I R A V I I

STATE OF Kansas, COUNTY OF Barton, SS

I, Floyd W. Smith, of the S & W DRILLING COMPANY, being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Floyd W. Smith

 Floyd W. Smith

Subscribed and sworn to before me this 23rd day of July, 1957.

Dean E. Hooley

 Notary Public

My commission expires: April 29, 1961.

RECEIVED
 STATE CORPORATION COMMISSION

AUG 17 1957
 08-17-1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 2 T. 12R. 15W
 BOOK PAGE 28 LINE 13