


15-167-00004-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 2 Twp. 12 Rge. 15 (E) (W) XX

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Morgenstern & Specter

Lease Name Shaffer Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 10-3-52 19

Application for plugging filed August 7, 1957 19

Application for plugging approved August 8, 1957 19

Plugging commenced 9-6-57 19

Plugging completed 9-14-57 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production August 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt

Producing formation Arnuckle Depth to top 3238 Bottom 3250 Total Depth of Well 3250 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	185	None
				5 1/2" OD	3239	465 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 3250 ft. Plugged off bottom with sand to 3225 and dumped 5 sacks cement with bailer. Shot 5 1/2 casing at 465 ft. Ran 8 joints tubing. Pumped mud and cement. Bailed out water to cement. Mudded to 35' and mixed 10 sacks cement for cap on well

STATE CORP. COM. REC. 09-23-1957 SEP 23 1957 CONSERVATION DIVISION Wichita, Kansas

Name of Plugging Contractor Forbes Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)  
Address St. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
(Address) Russell, Kansas

SUBSCRIBED AND SWORN TO before me this 21st day of September, 1957

My commission expires March 9, 1958

[Signature] Notary Public.

PLUGGING  
FILE SEC. 2 T 12 R 15 W  
BOOK PAGE 33 LINE 24


15-167-00004-00-00  
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 503 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.  
 Farm- Shaffer No. 1

SEC. 20 T. 12 R.15W  
 NE NE SW

Total Depth. 3250  
 Comm. 9-20-52 Comp. 10-3-52  
 Shot or Treated.  
 Contractor.  
 Issued. 12-6-52

County Russell  
 KANSAS



**CASING:**  
 8 5/8" 185' cem. w/125 sx.  
 5 1/2" 3239' cem. w/100 sx.

Elevation. 1775 K.B.  
 Phys.  
 Production. I.P. 141 bbls.

Figures Indicate Bottom of Formations.

shale & shells	340
sand & shale	520
shale & shells	590
red bed	835
anhyd.	870
shale & shells	1525
lime brkn	1585
lime & shale	2160
shale & shells	2420
shale & lime	2634
lime brkn	2680
lime & shale	2795
lime	2890
shale & lime	2935
lime	3238
Arbuckle	3250
Total Depth	

Tops:  
 Heebner 2882  
 Lansing 2935  
 Arbuckle 3238

KTD 3242

08-06-1957

<b>PLUGGING</b>
FILE SEC. 2 T. 12 R. 15W
BOOK PAGE 33 LINE 24