

15-167 06222-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

Russell County, Sec. 2 Twp. 12 Rge. 15 (W)

NORTH



Locate well correctly on above Section Flat

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SW NW  
Lease Owner Auto-Ordinance Corp.--Oil Division  
Lease Name Sutton Well No. 1  
Office Address 517 Union Natl Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 24, 19 43  
Application for plugging filed January 25, 19 43  
Application for plugging approved January 25, 19 43  
Plugging commenced February 9, 19 43  
Plugging completed February 12, 19 43  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Alexander, Great Bend, Kansas  
Producing formation Arbuckle Lime Depth to top 3270 Bottom 3310 Total Depth of Well 3310 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	290'	None
				5 1/2"	3270	2495'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Cement 3310 to 3244  
Mud 3244 to 290  
Cement 290 to 265  
Mud 265 to 18  
Cement 18 to Cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Auto-Ordinance Corp.--Oil Division  
Address 517 Union Natl Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS  
E. K. Edmiston (employee of owner) ~~owner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. K. Edmiston

517 Union Natl Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 8th day of March, 19 43

My commission expires 2-2-1944

Scott Stucky Notary Public



Sutton #1  
SW/4 NW/4 of Section 2-12S-15W,  
Russell County, Kansas  
Auto-Ordinance Corporation

15-167-06222-00-00

Commenced: Oct. 15, 1942  
 Completed: Nov. 22, 1942

Surface clay	0	10 :
Shale and shells	10	225
Sand	225	245
Red bed, shale and shells	245	305
Red bed and shale	305	330
Sand	330	445
Shale and shells	445	625
Red bed	625	725
Shale and shells	725	850
Anhydrite	850	895
Shale	895	1250
Salt and shale	1250	1330
Shale and streaks of salt	1330	1550
Shale and lime shells	1550	1570
Lime and shale	1570	1920
Lime	1920	2005
Shale and lime	2005	2050
Sandy lime	2050	2059
Lime and shale	2059	2095
Broken lime and shale	2095	2180
Lime and shale	2180	2400
Shale	2400	2515
Lime and shale streaks	2515	2560
Hard lime	2560	2565
Shale and lime	2565	2645
Broken lime	2645	2780
Lime, white	2780	2815
Lime	2815	2923
Shale and lime	2923	2942
Broken lime	2942	2980
K. C. Lime	2980	3014
Lime	3014	3054
Lime, hard	3054	3064
Lime, soft	3064	3074
Lime, hard	3074	3085
Lime	3085	3195
Shale various colors	3195	3212
Shale and lime	3212	3244
Shale and lime - chert	3244	3267
Shale	3267	3270
Arbuckle lime	3270	3297
Lime	3297	3310

TOTAL DEPTH 3310

CASING RECORD

10-3/4" Casing set at 295' and cemented  
 with 250 sacks of cement.  
 5-1/2" Casing set at 3270' and cemented  
 with 175 sacks of cement.

STATE OF OKLAHOMA )  
 )  
 COUNTY OF TULSA )

I hereby affirm that the above and foregoing is a true and correct copy of the log of your Sutton Well #1, located in the SW/4 NW/4 of Section 2, Township 12 South, Range 15 West, Russell County, Kansas.

HELMERICH & PAYNE, INC.

By William Goodkunst  
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 3rd day of December, 1942

Law Griffin  
 Notary Public

My commission expires July 22nd, 1943

2 12 15W  
 57 12

03-09-1943