

15-109-20003-00-00

M

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
9-19-1969  
SEP 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Yeoman Well No. 1

Location CSW-SW Sec. 7 Twp. 11 Rge. (E) (W) 36

County Logan Total Depth 4120'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 9:30 PM Day 12 Month 9 Year 1969

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1375'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement thru  
DP from 1600' to 1275'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/19/69

INV. NO. 498-w

Signed: A. L. Nichols  
Well Plugging Supervisor