



15-109-20013-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
12-23-1971  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: U. S. Signal Oil & Gas Company, 1971 Program,

Complete Address: 125 Central Building, Midland, Texas.

Lease Name: Collins Well No. 1

Location: CNW-NW Sec. 34 Twp. 11 Rge. (E)(W) 37

County: Logan Total Depth 5648' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

445'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1390'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 110 Cu. Ft. cement thru DP. Pull DP to 465' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*M. L. Nichols*  
Conservation Division Agent